



- * NO SUMP PUMP DRAINS TO BE CONNECTED.
- * NO BASEMENT DRAINS TO BE CONNECTED FROM THE FLOOR.
- * NO DOWN SPOUTS, FOUNDATION, FRENCH OR FIELD DRAINS TO BE CONNECTED.

- * 4" OR 6" P.V.C. SEWER PIPE S.D.R. 35 OR SCHEDULE 40 TO BE USED.
- * #57 STONE BEDDING AND COVER REQUIRED.
- * CLAY DAMS PERMISSIBLE TO STOP FLOW OF TRENCH WATER TOWARDS FOUNDATION AS NEEDED.
- * PROCEDURE TO BE FOLLOWED BY CONTRACTOR OR OWNER:
- EXCAVATE AT BUILDING AND TAP TO DETERMINE THE AMOUNT OF FALL BETWEEN THEM.

SERVICE SEWER DETAIL
N.T.S.